

| RISK ASSESSMENT PPE (Selection & Use of) | | Ref: P010 | | | | | | | |
|---|---|----------------------------------|----|--------------------|---|------------------------|----------------------------|--------|---|
| | | Page 1 of 1 | | | | | | | |
| EMPLOYER: Fastsource Ltd | | | | | | | | | |
| LOCATION: Calder Vale Road Wakefield | | | | | | | | | |
| ASSESSED BY: B Evans | | DESIGNATION: Yard Manager | | | | | | | |
| LEGEND: Likelihood and Severity:- 1 = Low 2 = Medium 3 = High Risk Rating (L x S):- 1-4 = Low (Acceptable) 6 = Medium (Consider further controls) 9 = Unacceptable (Do not proceed) | | | | | | | | | |
| SIGNIFICANT HAZARDS IDENTIFIED: Give a brief description of what could be reasonably expected to cause significant harm and how that harm may arise. | RISK ASSESSMENT | | | | | | | | |
| | UNCONTROLLED | | | CONTROLLED | | | | | |
| | L | S | RR | L | S | RR | | | |
| Falls of materials onto unprotected limbs/ head | 2 | 3 | 6 | 1 | 3 | 3 | | | |
| Inhalation of toxic or harmful substance | 2 | 3 | 4 | 1 | 3 | 3 | | | |
| Cuts to hands or body | 2 | 2 | 4 | 1 | 2 | 2 | | | |
| Crush injuries to feet, collision with plant | 2 | 3 | 6 | 1 | 3 | 3 | | | |
| Damage to eyes, damage to hearing | 2 | 2 | 4 | 1 | 2 | 2 | | | |
| PERSONS AT RISK: Employees undertaking activities. | | | | | | | | | |
| PERSONAL PROTECTIVE EQUIPMENT: The following PPE will be required for the work activities stated. Ensure the correct TYPE of PPE is selected. | | | | | | | | | |
| Head Protection | ✓ | Eye/Face Protection | ✓ | Hearing Protection | ✓ | Hi-visibility Clothing | ✓ | Gloves | ✓ |
| Foot Protection | ✓ | Safety Clothing | | R.P.E. | ✓ | Fall Arrest (in MEWP) | | | |
| CONTROL MEASURES: | | | | | | | | | |
| 1. | All persons to conform to site PPE rules. | | | | | | | | |
| 2. | All operatives are to ensure that skin remains covered during works. The wearing of shorts is strictly prohibited on all sites due to the nature of our operations. If skin comes into contact with any materials then it must be dealt with according to the manufacturer's recommendations immediately. | | | | | | | | |
| 3. | Hard hats to conform to the Construction Head Protection Regulations 1989. Any hat worn under a hard hat for warmth must be suitable to be worn with safety helmets, woollen hats/hoods/balaclava's not authorised for use with hard hats will not be permitted. | | | | | | | | |
| 4. | Operatives to check job specific method and risk packages prior to commencing to ensure the required PPE is worn in conjunction with that stated in the document. | | | | | | | | |
| 5. | For RPE a qualitative fit testing is usually adequate for disposable filter face pieces and half-masks. This is undertaken as a simple pass/fail based on the wearers' subjective assessment of the fit and leakage. This method is not suitable for full-face masks. Any worn or damaged items must be disposed off. Respiratory equipment - use an assigned protection factor of at least 20, even with water suppression equipment for cutting all silica based products use either FFP3 filtering face pieces or orinalasal respirators with P3 filters. The risk assessment for the designated task should provide the type of RPE required. | | | | | | | | |
| 6. | Hearing protection must be provided where noise levels exceed 85db(A), equipment should be kept in a safe clean location, insertion plugs should be disposed of at the end of the working shift, cups should be kept clean and inspected for damage prior to use. | | | | | | | | |
| 7. | Safety footwear should be worn at all times whilst on site, with steel toecaps and a midsole; lace up boots/shoes should be worn to ensure good ankle support. | | | | | | | | |
| 8. | Where a COSHH assessment/ risk assessment dictates gloves should be worn, these need to be free of damage and appropriate for the work being undertaken, all contaminated gloves should be disposed off. | | | | | | | | |
| 9. | Where plant is working in close proximity with site operatives, high visibility clothing should be worn at all times | | | | | | | | |
| Remember: Always check in your safety manual for Company safety procedures and systems of work. Refer to other assessments for activities connected with this assessment. | | | | | | | | | |
| ADDITIONAL CONTROL MEASURES: (Review at workplace and add any additional specific controls required) | | | | | | | | | |
| REVIEW AND MONITORING: Review in light of further information becoming available or a change in conditions/circumstances. | | | | | | | | | |
| INFORMATION TO BE PROVIDED TO EMPLOYEES: Information contained in this assessment. | | | | | | | | | |
| SIGNED BY ASSESSOR: <u>Bobby Evans</u> | | | | | | | DATE: November 2021 | | |